

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1965

6-8-65

CONSERVATION DIVISION
Wichita, Kansas

15-163-19074-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Robin Oil Co

Complete Address: 1322 E 50th St Tulsa, Okla

Lease Name Stamback Well No. 1

Location SW SW NW Sec. 33 Twp. 7 Rge. (E) (W) 17

County Rooks Total Depth 3367

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 7PM Day 2 Month 6 Year 65

The Above well was plugged as follows:

8 5/8" 210' circulated with cement - 5 1/2" 3363' with 100 sax cement
sand back to 3350', set 4 sax cement with dump bailer.

Pulled 2707' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2"
(27 sax gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to
200', displaced 20 sax cement through 5 1/2" at 200'. heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 6/8/65
INV. NO. 1289-W

Signed: Eason Petty
Well Plugging Supervisor