

DISTRICT CONSERVATION AGENT'S REPORT

B

15-163-02705-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 33 TWP. 7 RGE. 17 W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Scherpoit *Scha Charpiot*

Operator Murfin Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3406 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 140' circulated with cement. 5 1/2" at 3403' cemented to 2800' (survey)

Lane Wells plugs to 3154' top perforations at 3122'.

Filled with chat to 3110', set 4 sax cement with dump bailer, pulled Approx 2800' 5 1/2", filled hole with mud, pumped in 50 sax cement filling hole 151' to 0' with cement.

Cementing by Sun Cementing Co.

PLUGGING
FILE SEC 33 T 7 R 17 W
BOOK PAGE 49 LINE 43

RECEIVED
STATE CORP COM

J. J. [Signature]
District Conservation Agent

Date 10-2-52

CONSERVATION DIVISION
Wichita, Kansas

10-4-52