

DISTRICT CONSERVATION AGENT'S REPORT

R

TO: 15-163-02706-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 92-17
LOCATION SE NW NE
SEC. 35 TWP. 7 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease Hindman

Operator Alkay Oil Co Address 611 Kennedy Bldg Tulsa,

Field _____ County Rooks

Total Depth 3343 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 205' circulated with cement - 5 1/2" at 3095' with
125 sax cement behind - Cement and Baker plugs to 2900'-
perforated at 3776'.

Filled with chat to 2700', set 4 sax cement with dump bailer,
pulled 2400' 5 1/2". Filled with mud to 200', set rock and 20
sax cement, mud to 55', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC. 35 T. 7 R. 17W
BOOK PAGE 92 LINE 17

RECORDED
APR 21 1955
DIVISION

Edouard J. ...
District Conservation Agent

DATE 4-12-55

4-21-55