

DISTRICT CONSERVATION AGENT'S REPORT

15-163-03159-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 139-33
LOCATION CNW NW
SEC. 35 TWP. 7 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Kelley

Operator Co op Refg Assn Address Wichita, Kans

Field _____ County Rooks

Total Depth 3106 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 106' circulated with cement - 5 1/2" at 3072 cemented
and squeezed at 800' with 350 sax cement.

Filled with chat to 3060', set 4 sax cement with dump bailer.

Pulled 410' 5 1/2", mudded hole to 260' set rock to 230', 20 sax
cement at 230', mud to 35', set rock and 10 sax cement to

bottom cellar.

RECEIVED
STATE CORP. COM.
FEB 4 X 1952
2-4-52

PLUGGING
FILE NO. 139-35-17-R170
BOOK 139 LINE 33

[Signature]
District Conservation Agent
Date 1-31-52