



15-163-20421-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Coldwater of Alpine Drlg. has this  
date requested permission to plug the following described well:

Mr. Coldwater guarantees payment of the plugging fee.

Operator's full Name: Alpine Drlg., Inc. & Woodman-Iannitti Drlg.

Complete Address: 800 Bitting Bldg., Wichita, Ks.

Lease Name: Albright Well No. 1

Location: NE NE SE Sec. 36 Twp. 7 Rge. (E)(W) 18

County: Rooks Total Depth 3445' Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Coldwater was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210', set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo A. Marney  
Conservation Division Agent