



15-163-20320-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agents)

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1970
CONSERVATION DIVISION
Wichita, Kansas

8-19-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drlg. Company has this
date requested permission to plug the following described well:

Mr. Murfin Drlg. Co. guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas 67202

Lease Name: Riffe Well No. # 1

Location: SE SE NE Sec. 7 Twp. 7 Rge. 19 (E) (W) W

County: Rooks Total Depth 3550 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dean Ulrich was instructed to plug the well as follows:

8 5/8" 206' Cwc.

Circulated hole with heavy mud to 750', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 200' & displaced 20 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Sun Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don Luman
Conservation Division Agent