



15-163-21308-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1982
CONSERVATION DIVISION
WICHITA, KANSAS

323-82

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Virgil Hagen of Russell Supply Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Russell Supply Co.

Complete Address: P.O. Box 73 - Russell, Kansas 67655

Lease Name: Stice Well No. 1

Location: NW14 Sec. 6 Twp. 7 Rge. 19 (E) (W)

County: Rooks Total Depth: 3575'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Virgil Hagen was instructed to plug the well as follows:

NOTE: Well record provided by Mr. Hagen.
8 3/8" set @ 300' w/225 SX (8 3/8" set @ 300' w/150 SX) 5 1/2" set @ 3569' w/150 SX
Open Hole 3569-75 - Top perf. 3310' - No plug back - Recovered 1700'
of 5 1/2" casing (L-K Wireline; Hays, Kas.?) - Mr. Hagen was instructed to run
tubing to approx. 1800' - pumped in 3 hulls -> 13 gel. -> 50 emt. ->
6 bbl water -> 20 gel -> 200 emt -> 6 gel -> 50 emt. -> MAX. P.S.T.
600# -> shut in P.S.F. 250# - (Hagen did not run tubing - pumped into 8 3/8" casing)
(emt. by Sun)
(Red)

Very truly yours,

Dennis L. Hamel
Conservation Division Agent