



15-163-20095-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
60-21-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Midwestern Supply Company, Incorporated,

Complete Address: 207 Brown Building, Wichita, Kansas.

Lease Name: Maddy Well No. 1

Location: NW-NW-SW Sec. 36 Twp. 7 Rge. (E)(W) 18

County: Rooks Total Depth 3383' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

213'---8 5/8" Surface casing, cement circulated with 140 Sx.  
3365'---4 1/2" Production casing cemented on bottom with 100 Sx. Bridge plug set above perforations. Well flowing from Dakota break-in.

Squeeze 4 1/2" casing with 5 sacks hulls, 25 sacks gel and 60 Sx. cement.  
Squeeze annulus with 100 Sx. cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent