



15-163-20093-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JAN 2 1968
1-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wynn of Gabbert-Jones Drlg. has this date requested permission to plug the following described well:

Mr. Wynn guarantees payment of the plugging fee.

Operator's full Name: Mark Richardson

Complete Address: 502 Union Center Bldg., Wichita, Ks.

Lease Name: Maddy Well No. 1

Location: SE SE SW Sec. 35 Twp. 7 Rge. 18 (E)(W) X

County: Rooks Total Depth 3470' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wynn was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing pl

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Geo. F. Massey
Conservation Division Agent