

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 009-21291-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Mai Oil Operations, Inc. KCC License #: 5259
(Owner / Company Name) (Operator's)

Address: P.O. Box 33 City: Russell

State: Kansas Zip Code: 67665 Contact Phone: (785) 483-2169

Lease: Monroe Well #: 4 Sec. 4 Twp. 16 S. R. 13 East West

NW - SW - SW Spot Location / QQQQ County: Barton

900 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 327' Cemented with: 195 Sacks

Production Casing Size: 4 1/2" Set at: 3379 1/2' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open hole 3379 1/2'-3381'

Elevation: 1929 (G.L. / K.B.) T.D.: 3381' P.B.T.D.: 3381' Anhydrite Depth: 881'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Plug back open hole w/sand and cement, rip casing and plug while pulling casing

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Allen Bangert

Phone: (785) 483-2169

Address: P.O. Box 33 City / State: Russell, Ks. 67665

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W. Main, Lyons, Ks. 67554 Phone: (620) 257-2719

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-11-05 Authorized Operator / Agent: Allen Bangert
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 21 2005
KCC WICHITA

DRILLER'S WELL LOG

DATE COMMENCED: 11-21-77
DATE COMPLETED: 11-26-77

Al Tipton
Monroe #4
900' S - 330' W of SW/4
Sec. 4-16-13W
Barton County, Kansas

ELEVATION: 1926' K.B.
1921' G. L.

FORMATION DATA

0- 881' Shale and Sand Streaks
881- 913' Anhydrite
913-3052' Shale and Lime
3052-3057' Shale
3057-3074' Lime
3074-3089' Lime
3089-3134' Shale
3134-3329' Lime
3329-3378' Lime and Shale
3378-3381' Dolomite
3381' RTD

Anhydrite 881
Heebner 3052
Toronto 3074
Douglas 3089
Lansing 3134
Base Kansas City 3329
Arbuckle 3378
RTD 3381

RECEIVED
NOV 21 2005
KCC WICHITA

SURFACE PIPE:

Ran 8 Jts. used 28# 8 5/8" Casing.
Tally 324'. Set @ 327' w/195 sks.
cement, 2% Gel, 3% c.c. By Sun
Cementing. P.D. @ 1:45.
Cement did circulate.

PRODUCTION PIPE:

Ran 90 Jts. new and used 4 1/2" 9.5#
Casing. Tally 3396.73. Set @ 3379 1/2'
w/100 sks. 60-40 Pozmix, salt
saturated. By Sun Cementing.


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale Smith

Subscribed and sworn to before me this 28th day of November 1977.



Notary Public

My commission Expires: 1-28-1980

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Mai Oil Operations, Inc.
4514 Cole Ave., STE 740, LB 30
Dallas, TX 75205

November 29, 2005

Re: MONROE #4
API 15-009-21291-00-00
S2NWSWSW 4-16S-13W, 900 FSL 330 FWL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor