

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23332-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: Mull Drilling (owner/company name) KCC LICENSE # 5144 (operator's)

ADDRESS: P.O. Box 2758 CITY: Wichita
STATE: Kansas ZIP CODE: 67201-2758 CONTACT PHONE: 316-264-6366
LEASE: Leo WELL#: 1-26 Section 26 Township 21s Range 13w
S/2 NW NW SPOT LOCATION/QQQQ COUNTY: Stafford

1200 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)
330 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS
SURFACE CASING SIZE 8-5/8" SET AT 280' KB CEMENTED WITH 275 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1870 G.L. 1879 K.B. T.D. 3800 P.BTD. _____ Anhydrite Depth 693
(Stone Corral Formation)
CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugging orders from Mike Maier on 11/17/05. Plugged with 175 sks 64/40 Poz, 6% Gel & 1/4# Flo-seal. Heavy mud in hole and between all plugs. Bottom plug at 3473' - 50 sks, 2nd plug at 750' - 40 sks, 3rd plug at 290' - 50 sks and top plug at 60' - 20 sks. Rathole - 15 sks, no mousehole. Job completed at 4:30 pm on 11/17/05.
Allied Cementing ticket # 22595. Sterling reported plugging to KCC 11/18/05.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Lonnie Saloga Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 4:30 pm on November 17, 2005.
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 11/17/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED
NOV 22 2005
KCC WICHITA

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Leo 1-26

LOCATION: S/2 NW NW
API: 15-185-23332-0000

Section 26 T 21s R 13w
Stafford County, Kansas

OWNER: Mull Drilling
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 08-Nov-05
COMPLETED: 17-Nov-05

TOTAL DEPTH: DRILLER 3800 FEET
LOGGER 3798 FEET

Ground Elevation: 1870
KB Elevation: 1879

LOG

0 -	2 FEET	Top Soil	From Water Well Driller
2 -	18 FEET	Clay	
18 -	25 FEET	Fine Sand	
25 -	50 FEET	Clay	
50 -	75 FEET	Fine Sand	
75 -	100 FEET	Sand and Gravel	
100 -	715 FEET	Redbeds	
715 -	735 FEET	Anhydrite (Driller's)	
735 -	1550 FEET	Shales and Salt	
1550 -	3650 FEET	Limestone, Shale and Dolomite	
3650 -	3800 FEET	Arbuckle	

CASING RECORDS

Surface Casing-8-5/8"

Spud at 1:45 pm on 11/08/05. Drilled 12-1/4" hole to 280'. Ran 6 joints of new, 20#, 8-5/8" surface casing, tallied 265.17', set at 280' KB. Cemented with 275 sx 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 8:00 am on 11/08/05. Allied Cementing ticket # 22591. Welder strapped bottom 3 joints together and welded collars on remaining joints.

Production Casing

Plugging orders from Mike Maier on 11/17/05. Plugged with 175 sks 64/40 Poz, 6% Gel & 1/4# Flo-seal. Heavy in hole and between all plugs. Bottom plug at 3473' - 50 sks, 2nd plug at 750' - 40 sks, 3rd plug at 290' - 50 sks and top plug at 60' - 20 sks. Rathole - 15 sks, no mousehole. Job completed at 4:30 pm on 11/17/05. Allied Cementing ticket # 22595. Sterling reported plugging to KCC 11/18/05.

DEVIATION SURVEYS

3/4 degree(s) at 280 feet
1 degree(s) at 3325 feet
1-1/2 degree(s) at 3569 feet

RECEIVED
NOV 22 2005
KCC WICHITA