

12-21-95

DEC 21 1995

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)
CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-163-22,807-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Alcona Oil Company KCC LICENSE # 7419
(owner/company name) (operator's)

ADDRESS 2908 Hillcrest Dr. CITY Hays

STATE Kansas ZIP CODE 67601 CONTACT PHONE # (913)-628-2899

LEASE Riseley "A" WELL# 1 SEC. 17 T. 7s R. 20 ~~East~~/West

C - S/2 - NE - NE SPOT LOCATION/QQQQ COUNTY Rooks

4290 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE none SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 264' CEMENTED WITH 160 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 3670' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3637-3643; 3625-3630; 3565-3568

ELEVATION 2151' GL T.D. 1580', circulated cement to the surface.
(G.L./K.B.) P.B.T.D. 3680' ANHYDRITE DEPTH 1684'
(Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per KCC Dist. #4 Squeezed 4 1/2 csg as follows; Mix and pump 200 sx of 60/40 poz 10% gel with 500# hulls. Max 1000P.S.I. Shut-in 700#. Pressure up 8 5/8" S.P. to 500 P.S.I.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dean LeSage PHONE# (913)-628-2899

ADDRESS 2908 Hillcrest Dr. City/State Hays, Ks 67601

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P.O. Box 31, Russell, KS 67665 PHONE # (913) 625-3019

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 12-12-95 10:00 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-12-95 AUTHORIZED OPERATOR/AGENT: Dean LeSage
(signature)