

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22662-00-00
Spot: W2SWNENE Sec/Twnshp/Rge: 35-11S-20W
4290 feet from S Section Line, 1200 feet from E Section Line
Lease Name: CONELL Well #: 2-35
County: ELLIS Total Vertical Depth: 4028 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3828	0	w/200 sxs cmt
SURF	8.625	204	0	w/165 sxs cmt

91
\$130

Well Type: SWD UIC Docket No: D20724.0 Date/Time to Plug: 10/12/2005 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 700# hulls.
DV Tool at 1529' w/400 sxs.
06/03/1999 - squeezed 4088' w/40 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2005 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied rigged up to 4 1/2" casing and pumped 325 sxs 60/40 pozmix - 10% gel with 700# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3828	4028	OH	

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 11-23-05

NOV. NO. 2006046780

RECEIVED

NOV 23 2005

KCC WICHITA

NOV 16 2005

MURFIN DRILLING CO

617 UNION CENTER

WICHITA, KS 67202

CONTR COMPANY TOOLS

#2-35 CONELL

CTY ELLIS

35-11-20W

990' FNL &

1200' FEL, NE/4

GEOL _____ FIELD STAR NW CONF

E 2121 KB CM 10/16/81 CARD ISSUED 3/4/82 IP SWDW

API 15-051-22,662

ARB OH 3829-4020 OA

	+		▲
	+		+

SMP	TOPS	DEPTH	DATUM
SC		1506	+ 615
B SC		1548	+ 573
TOP		3160	-1039
HEEB		3383	-1262
TOR		3403	-1282
LANS		3422	-1301
B KC		3654	-1533
PENN CGL		3725	-1604
ARB		3798	-1677
RTD		4020	-1899

204 w 1655x 4 1/2 w 200 x
 8-5/8" 780/285x, 2" 3829/688x
 PV 1529' w 400 x/s.

DST (1) 3441-63(LANS)/TIMES NA, REC
 75' WCM W/SSO, SIP 1196-1163#, FP
 55-66/72-90#, HP 1961-1959#

DST (2) 3463-3505(LANS)/TIMES NA, REC
 315' WCM, 20' W, SIP 1175-1163#, FP
 197-350#

DST (3) 3536-3605(LKC)/TIMES NA, REC
 360' WCM, SIP 1121-1067#, FP 77-
 154/164-252#, HP 1994-1972#

MICT - CO, (ARB OH) 3829-4020, AC 500
 G, POP, SWDW, INJECTION RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS