

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03204-00-02
Spot: NENWSW Sec/Twnshp/Rge: 5-9S-17W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: THOMPSON Well #: 3
County: ROOKS Total Vertical Depth: 1754 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	202	0	UNKNOWN

5701

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2005 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CHARLES FARR Company: LIBERTY OPER & COMPL, INC. Phone: (785) 434-4686

Proposed Plugging Method: Ordered 186 sxs 60/40 pozmix - 10% gel and 200# hulls.
Ordered 250 sxs 60/40 pozmix - 10% gel and 500# hulls.
Out of casing at 1300' - stuck at 1740' - shot off tubing at 1320'.
Anhy. 1305' - 1335'.
Bad casing at 1210' to 1310'.
Unable to washover tubing and bit. Decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2005 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 1322'. Allied pumped 180 sxs 60/40 pozmix - 10% gel with 200# hulls - ran out of cement.
Pulled tubing to 880' - waited on cement.
Pumped 40 sxs cement with 150# hulls - cement circulated.
PTOH. Squeezed 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Note: Lost 14 joints of tubing and 4 7/8" bit in hole.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

100-
INVOICED
DATE 11.29.05
INV. NO. 2006060790

RECEIVED

NOV 28 2005

KCC WICHITA

Form CP-2/3

NOV 22 2005

