

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20429-00-00

Spot: N2NWNW

Sec/Twnshp/Rge: 24-4S-22W

4950 feet from S Section Line, 4620 feet from E Section Line

Lease Name: DIANA

Well #: 1

County: NORTON

Total Vertical Depth: 3632 feet

Operator License No.: 8914

Op Name: H & C OIL OPERATING INC.

Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3628	0	100 SX CMT
SURF	8.625	213	0	150 SX CMT

\$ 118⁰⁴

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/15/2005 12:30 PM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: CHARLES R RAMSAY

Company: H&C OIL OPERATING, INC.

Phone: (785) 737-3174

Proposed
Plugging
Method:

Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/15/2005 3:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech set CIBP at 3620' w/5 sxs cement on top.
Shot casing off at 1815' - tight - shot casing at 1005' free.
Allied pumped 125 sxs cement with 500# hulls - pulled casing to 774'.
Allied pumped 40 sxs cement. Max. P.S.I. 700#. Pulled to 212'.
Allied pumped 25 sxs - circulated cement.
Pulled casing out of hole. Topped off with 10 sxs cement - hole full.

Perfs:

Top	Bot	Thru	Comments
3632	3647	OH	

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

110
INVOICED

DATE

11-29-05

INV. NO

2006060787

RECEIVED

NOV 28 2005

KCC WICHITA

Form CP-2/3

NOV 21 2005

H & C OIL OPERATING
PLAINVILLE KS 67663

24-04S-22W
C N/2 NW NW

#1 DIANA

site 3-1/2 N & 3/4 W OF DENSMORE KS
contr: DISCOVERY DRILLING #1
geo: RON NELSON
fr date 02/18/2005
spc date 03/03/2005
drig comp 03/07/2005
city: NORTON
field: HANSEN ESTATE NE EXT (1/8 S)
APR 15-137-20429
card issued 07/25/2005
last revised 07/25/2005

ELV: 2167 KB, 2159 GL LOG
tops.....depth/datum
ANH.....1830 +337
B/ANH.....1856 +311
HEEB.....3341 -1174
TOR.....3369 -1202
LANS.....3386 -1219
BKC.....3574 -1407
ARB.....3630 -1463
RTD.....3632 -1465

IP status

TEMP ABD, 04/18/2005

CSG: 8-5/8" 213 / 150 SX (ALT 2), 5-1/2" 3628 / 100 SX

COMMENT: MI & RURT 3/3/2005

NO CORES OR DSTS

TRGT ZN: LKC, ARB (OIL), PTD 3625 (ARB), MICT - CO,
(ARB OH), AC 250 GAL (15%), SWB LD, RE-AC 1000 GAL
(15%), SWB LD, RE-AC 1500 GAL (15%), SWB LD, RE-AC
2000 GAL (15%), NON-COMMERCIAL, SI - EVAL, TEMP ABD
(4/18/2005) - NO OTHER INFO AVAILABLE - TEMP COMP
7/25/2005

COPYRIGHT 2005
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS