

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20023-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 4-20S-11W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: STATE Well #: 2  
County: BARTON Total Vertical Depth: 3316 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3306	0	125 SX CMT
SURF	8.625	238	0	225 SX CMT

#107 77

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2005 2:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROESCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Low casing leak. Low fluid 1122'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2005 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing with a swedge and pumped 190 sxs cement with 500# hulls mixed in to circulate cement out of backside of 8 5/8" casing.  
Shut in 8 5/8" casing and pumped an additional 40 sxs.  
Max. P.S.I. 550#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3306	3316		

Remarks: ALLIED CEMENTING COMPANY-TICKET #22599.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_  
(TECHNICIAN)

INVOICED

DATE

11.29.05

WELL NO

2006060792

RECEIVED

NOV 28 2005

KCC WICHITA

Form CP-2/3

NOV 23 2005

JAYHAWK OIL COMPANY #2 STATE 4-20-11W  
 Contr. ISEBN DRLG CO. Cty. BARTON NW SW NW  
 Geol. JIM DEVLIN Pool CHASE-SILICA  
 E. 1778 KB. Cm. 3/8/67 Cp. 3/23/67 IP PMP 91 BOPD/NW  
 ARB 3306-16


SMP Tops	Depth	Datum
HEEB	2903	-1125
DOOG	2935	-1157
BR LM	3023	-1245
LANS	3045	-1267
ARB	3303	-1525
RTD	3313	-1535
DDTD	3316	-1538

Csg. API 15-009-20,023  
 8" 238/225 sx; 5" 3306/125 sx;  
 DST 2930-80/1', G/10", TSTM, 19G'  
 GSY OCM, (25% O), 420' G&OCMW  
 FBHP 570#; FP 333-381#;  
 DST 3305-13/2', 180' GIP, 480' CL  
 GSY OIL, 540' SLI MDY GSY OIL  
 BHP 718-681#; FP 95-410#;  
 RTD 3313; DD TO 3316 TD; SWB 9 HRS  
 , SWB 4.64 BOPH, NW, T&R, POP.

NO LOG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 MAR 28 1967  
 11:00 AM