

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00874-00-00
Spot: NENWSW Sec/Twnshp/Rge: 29-5S-20W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PINKERTON Well #: 11
County: PHILLIPS Total Vertical Depth: 3652 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3645	0	w/150 sxs cmt
SURF	8.625	199	0	w/250 sxs cmt #11869

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2005 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement and 700# hulls.
No squeeze records. Will perforate 1150' and 1800'.
Arbuckle perfs: 3631' - 3642'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2005 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1800' and 1150' - one shot each.
Ran tubing to 3602'. Swift Services pumped 80 sxs SMD with 300# hulls.
Pulled tubing to 1850'. Swift Services pumped 95 sxs SMD with 300# hulls - cwc.
PTOH. Squeezed with 15 sxs SMD.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to backside and pumped 15 sxs SMD.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3645	3652	OH	

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams

(TECHNICIAN)

INVOICED

RECEIVED

DATE 11.29.05

NOV 28 2005

INV. NO 2006060792

KCC WICHITA

Form CP-2/3

NOV 22 2005

CITIES SERVICE OIL CO., #11 PINKERTON Arb 29-5-20W
 NE NW SW
 Contr. PHILLIPS County
 E2231 Comm. 2-2-49 Comp. 3-18-49 IP 2520 90PD DEP THO

Tops	Depth	Datum
TOP	3157	-926
HEEB	3350	-1119
LANS	3395	-1164
A+B	3630	-1399
REAG	3642	-1411
T.D.	3652	-1421

Casing
 8" 203 2700' CIL/12 HRS: PERF
 5" 3645 43S, 3631-42: ACID 1000:
 54 BO & 127 BW/12 HRS:
 ACID 1000: PMP 102 BO,
 25% WTR/9 HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

03230
 03230
 03230