

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00875-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 29-5S-20W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: PINKERTON Well #: 12  
County: PHILLIPS Total Vertical Depth: 3652 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3642	0	w/150 sxs cmt
SURF	8.625	198	0	w/250 sxs cmt

#118 69

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2005 3:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement and 600# hulls.  
PBTD 3638'. No squeeze records.  
Perforate 1150' and 1800'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2005 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1150' and 1800'.  
Ran tubing to 3602'. Swift Services pumped 80 sxs SMD with 300# hulls.  
Pulled to 1850'. Swift Services pumped 95 sxs SMD with 300# hulls - circulated cement.  
PTOH. Squeezed with 10 sxs SMD.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside. Pumped 15 sxs SMD.  
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3618	3622		

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 11-29-05

INV. NO. 2006060792

RECEIVED

NOV 28 2005

KCC WICHITA

Form CP-2/3

NOV 22 2005

CITIES SERVICE OIL CO. #12 PINKERTON Arb 29-5-20W  
NE SW SW

Contr. \_\_\_\_\_ PHILLIPS County \_\_\_\_\_

E. 2233 Comm. 2-21-49 Comp. 4-1-49 IP 1272 BOPD

Tops	Depth	Datum	Casing
HEEB	3353	- 1120	8" 198 5" 3642
LANS	3396	- 1163	
B/KC	3592	- 1359	
ARB	3633	- 1400	
BASAL SD	3642	- 1409	
T.D.	3652	- 1419	

FMP 238 BO/12 HRS

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS
