

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01328-00-00
Spot: SWNE Sec/Twnshp/Rge: 33-8S-16W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ADAMS A Well #: 1
County: ROOKS Total Vertical Depth: 3295 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3295	0	w/unknown sxs cmt
SURF	8.625	187	0	w/136 sxs cmt

10709

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2005 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 250 sxs cement.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2005 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

1967 - Squeezed at 768' w/250 sxs cement.
09/16/1999 - 2 3/8" tubing set at 3068' w/250 sxs cement.
Tied to 2 3/8" tubing - squeezed 100 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Tied to 5 1/2" x 2 3/8" annulus to squeeze - took no cement.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 70 sxs cement.
Max. P.S.I. 200#.
Total of 170 sxs 60/40 pozmix - 10% gel.
Dakota 477' - 777'. Anhydrite 1181' - 1211'.

Perfs:

Top	Bot	Thru	Comments
3234	3237		
3223	3226		
3205	3209		
3137	3140		
3098	3102		
3080	3086		

Remarks: ALLIED CEMENTING COMPANY. FLATLAND TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED
DATE 11.29.05
INV. NO. 2006060793

RECEIVED
NOV 28 2005
KCC WICHITA

Form CP-2/3

NOV 21 2005

#1 102

7018

MAOICER

7-7

MURFIN DRLG & R COMEAU #1 ADAMS 'A' 33-8-16W
C SW NE

Contr. MURFIN DRLG ROOKS County

E 1932 RB Comm. Comp. 9-22-61 IP 25 BOPD/KC

Tops	Depth	Datum
ANH	1181	-751
TOP	2781	-849
HEEB	3003	-1071
TOR	3022	-1090
KC	3043	-1111
B/KC	3275	-1343
TD	3295	-1363

Casing
8" 187
5" 3295

PERF 12/3234-37: 12/3223-26:
16/3205-09: 12/3137-40: 16/3098
-3102: 24/3080-86: ACID 9000:
CO: PMP 10 BOPD

LATON POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS