

6 050177

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,644-00-00
SW SE SW, SEC. 21, T. 7 S, R. 20 WXX

330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name Deloris Well # 1-21

Operator: Universal Resources
Name & Address 1800 Denver Nat'l Bank Plaza
Denver, Colorado 80202

County Rooks 116.03

Well Total Depth 3570 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 255 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita,

Company to plug at: Hour: PM Day: 11 Month: MARCH Year: 19 85

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling (phone) _____

were: Order 205 lbs. 50/50 pozmix 6% gel 3% cal. cl. 1 sk flo-cel and 8⁵/₈" plug.

1 sk hulls. Spot with drill pipe with no less than 35 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXX

Operations Completed: Hour: 5:15 PM Day: 11 Month: MARCH Year: 19 85

ACTUAL PLUGGING REPORT

1st plug @ 3520 w/20 sks

2nd plug @ 1640 w/25 sks

3rd plug @ 960 w/100 sks 1 sk flo-cel

4th plug @ 280 w/40 sks

5th plug @ 40 w/8⁵/₈" plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole
Remarks: Cemented by Halliburton

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1985
3-18-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Gilbert P. Hecker / SH (TECHNICIAN) 3-15-85

3-19-85
7401
INV. NO. 3-11