

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22307-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 7-11S-23W
820 feet from S Section Line, 330 feet from W Section Line
Lease Name: HERMAN OIL COMPANY Well #: 1
County: TREGO Total Vertical Depth: 3920 feet

Operator License No.: 33657
Op Name: OHIO KENTUCKY OIL CORPORATION
Address: THE WILLIAM M. GRIFFITH BUILDING
LEXINGTON, KY 40503

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

\$127⁴⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/06/2005 5:00 PM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: DON ANDERSON Company: OHIO KENTUCKY OIL COMPANY Phone: (859) 276-3500

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 11/06/2005 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 1880' w/25 sxs.
2nd. Plug at 910' w/100 sxs.
3rd. Plug at 269' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 11.23.05
VV NO 2006060781

RECEIVED

NOV 23 2005

KCC WICHITA

Form CP-2/3

NOV 16 2005