

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-121-28116-00-00
Spot: NWSW Sec/Twnshp/Rge: 12-16S-24E
1980 feet from S Section Line, 500 feet from W Section Line
Lease Name: SOMEDAY Well #: 42-12
County: MIAMI Total Vertical Depth: 640 feet

Operator License No.: 32294
Op Name: OSBORN ENERGY, L.L.C.
Address: 24850 FARLEY
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		

35⁰⁰

Well Type: GAS DH UIC Docket No: _____ Date/Time to Plug: 11/14/2005 9:30 AM
Plug Co. License No.: 5885 Plug Co. Name: GLAZE, SUSIE DBA R.S. GLAZE DRILLING
Proposal Rcvd. from: SUSIE GLAZE Company: GLAZE, SUSIE DBA R.S. GLAZE DR Phone: (913) 592-2033

Proposed Plugging Method: Fifty ft plug at TD. Fifty ft plug at 500 ft. 350 ft to surface.

Plugging Proposal Received By: FRANK GUILFOYLE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2005 12:30 PM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

Perfs:

Drill steel at T.D. Pump 15 sacks of 60/40 POZ mix for 50 ft. plug. Pull steel to 500 ft., and pump 20 sacks for 50 ft plug. Pull steel to 350 ft and fill to surface. Pull pipe and top off. Pumped 115 sacks from 350 to surface. Total of 150 sacks of 60/40 POZ mix. Well plugged.

RECEIVED
KCC DISTRICT #3

NOV 18 2005 FG

CHANUTE, KS

Remarks: WELL WAS D & A.

Plugged through: DP

District: 03

Signed

Frank Guilfoyle
(TECHNICIAN)

INVOICED

DATE

11.23-05

INV. NO

2006060782

RECEIVED

NOV 23 2005

KCC WICHITA