

6 070761

4-21

API NUMBER 15- 163-23,039 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW SE NE, SEC. 21, T 7 S, R 20 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
3630 feet from S section line
990 feet from E section line

Operator License # 4981 Lease Name Bellerive Well # 2-21

Operator: Cholla Res Inc. County Rooks 116.68

Name & Address 1641 California St. #400 Well Total Depth 3590 feet

Denver, Colorado 80202 Conductor Pipe: Size 0 feet

William Goff Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well Input Well SMD Well U&A X

Other well as hereinafter indicated 5-10-89

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, Ks.

Company to plug at: Hour: AM Day: 21 Month: April Year: 19 89

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 303-623-4565

were: 8 5/8" 206' S.P. cwc w/140 sks 60/40 poz 2% gel 3% cal cl. By Allied Cement.

Arbuckle at 3540' Elv. 2068' Anhy 1661'; No circulation problems. Mud condition 50 vis

9.4 weight - 92 water loss. Proposal 245 sks 60/40 Poz 6% gel. Spot with drill stem,

circulate, heavy mud between all plugs. 30 sks at 3480'; 30 sks at 1630'; 100 sks w/1 F.C.

at 960'; 50 sks at 270'; 10 sks at 40'. 15 sks rathole (cir).

Plugging Proposal Received by MJS (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 4:45 AM Day: 21 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Ordered 245 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem circulated heavy mud between all plugs.

1st plug at 3480' w/30 sks cement 5th plug 10 sks at 40'

2nd plug at 1630' w/30 sks cement 15 sks in rathole (cir)

3rd plug at 960' w/100 sks w/1 sk F.C. 10 sks mousehole (cir)

4th plug at 270' w/50 sks cement. By Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOLVED I hereby certify that I have observed this plugging.

Partial Witness by Dale Balthazor

DATE 5-11-89

INV. NO. 24758

Signed Marion J. Schmidt (TECHNICIAN)