

6 030424

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22,667-00-00

SWNESE SEC. 17, T. 7 S. R. 20 W. 4

1780 feet from N/S section line

960 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7419

Lease Name Kellogg Well # 1

Operator: Alcona Oil Co.

County Rooks 118.63

Name & Address RR 2 Box 51

Well Total Depth 3650 feet

Stockton Kansas

Conductor Pipe: Size \_\_\_\_\_ feet

67669

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pioneer Drilg. License Number 5665

Address Plainville Kansas.

Company to plug at: Hour: AM Day: 22 Month: 4 Year: 19 85

Plugging proposal received from John walker

(company name) Pioneer Drilg. (phone) \_\_\_\_\_

were: 8 5/8 set @ 260 w/ 200 sp. With no loss of fluid and no less

than 36 vis. mud in hole spot cement plugs with 4 1/2" D.P.

Order 215 sp 50/50 sp 6% gel 3% cc 1% Cello Flake 8 5/8 W.P. Allied

Com. Co. from pond.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1985

4-29-85

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:15AM Day: 22 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Spot D.P. @ 3645 displace 25 sp. Com. mix.

laydown D.P. to 1675 displace 25 sp Com. mix. laydown D.P.

to 1000' displace 100 sp Com mix 1% Cello flake. laydown D.P.

to 265' displace 40 sp Com. mix. laydown D.P. Push W.P. to

Kelly depth fill hole with cement mix to bottom collar.

displace 15 sp Com. mix. in rat hole with joint of D.P.

Remarks: Plugging Complete. Elav. 2133KB only 1665-97 arb. 3644 near Prod.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 5-6-85

Signed Carl Goodrow

INV. NO. 7952

(TECHNICIAN)

MAY 22 1985

18  
4-26-85  
mgf