

4-041741

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-22,807-00-00

12-12

S2 NE NE /4 SEC. 17, 07 S, 20 W  
4290 feet from S section line  
660 feet from E section line

Operator license# 7419

Lease: Riseley "A" Well # 1

Operator: Alcona Oil Company

County: Rooks

Address: 2908 Hillcrest Dr.  
Hays, Kansas 67601

Well total depth 3680 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 264 feet  
w/160 sxs

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 12 Month: December Year 1995

Plugging proposal received from: Dean LeSage

Company: Alcona Oil Company Phone: 913-628-2899

Were: 4 1/2" casing set at 3670' w/150 sxs cement. Perfs at 3637' - 3643' - 3625' - 3630' - 3565' - 3568'. PBSD at 3651'. Anhy. 1684'. Elev. 2151'. 1580' circulated cement to the surface.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 10:30 A.M., Day: 12, Month: December, Year: 1995

Actual plugging report: R.U. cementers to squeeze 4 1/2" casing as follows: mixed and pumped 200 sxs of 60/40 pozmix - 10% gel with 500# hulls. Max. P.S.I. 1000#. S.I.P. 700#. Pressured-up 8 5/8" S.P. to 500# P.S.I.

STATE CORPORATION COMMISSION

DEC 26 1995

12-26-95

Remarks:  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC , NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING . Elevation: 2151 GL

I did[ X ] / did not[ ] observe the plugging.

Dennis L. Hamel  
(agent)  
Form CP-2/3

12-27-95  
44351  
INVOICED  
DATE 12-27-95  
INV. NO. 44351

HD.