

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1962
CONSERVATION DIVISION
Wichita, Kansas
5-15-62

WELL PLUGGING APPLICATION FORM
File One Copy

15-163-00223-00-00

Lease Owner Morgenstern & Specter Inc.
(Applicant)
Address P.O.Box 661 Russell, Kansas

Lease (Farm Name) Griebel Well No. 1

Well Location NE NE NW Sec. 8 Twp. 7 Rge. 19W (E) (W)

County Rooks Field Name (If any)

Total Depth 3438 Oil Well Gas Well Input Well SWD Well D & A

Was well log filed with application? Yes If not, explain:

Date and hour plugging is desired to begin May 15, 1962


Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner Ralph Lynch
Address Pawnee Rock, Kansas

Plugging Contractor Lynch Casing Pulling Co. License No.
Address R.R. #3 Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to Morgenstern & Specter Inc.
Address Box 661 Russell, Kansas

and payment will be guaranteed by applicant.

Signed: 
Applicant or Acting Agent

Date: May 14, 1962

15-163-00223-06-00

COPY

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SAM PACK
Farm - Griebel


No. 1

SEC. 8 T. 7 R. 19W
NE NE NW

Total Depth. 3456
Comm. 11-29-48 Comp. 12-11-48
Shot or Treated. acidized with 500 gal re-acidized with 1500 gal
Contractor. Braden & Greene Drilling Co.
Issued. 6-18-49

County. Rooks

KANSAS



CASING:

8 5/8" 216'17"
5 1/2" 3454' ccm w/100sx

Elevation. _____

Production. 25 BOPD

Figures Indicate Bottom of Formations.

| | |
|-------------------|------|
| Shale | 30 |
| sand | 40 |
| sand, shale | 100 |
| shale, shells | 210 |
| shale | 590 |
| sand | 605 |
| shale | 830 |
| sand, shalo | 980 |
| sand | 1220 |
| sand, shale | 1230 |
| iron, sand | 1280 |
| shale, sand | 1335 |
| red rock, shalo | 1515 |
| a nhydrite | 1555 |
| shalo, red rock | 1570 |
| shale, sdy, sholl | 1930 |
| limo, shalo | 2815 |
| limo, shalo | 2875 |
| shalo | 2965 |
| shale, limo | 3060 |
| limo | 3105 |
| limo, shalo | 3230 |
| limo | 3265 |
| limo, shalo | 3380 |
| shalo, limo | 3455 |
| limo | 3456 |
| Total Depth | |

TOPS:

| | |
|----------|------|
| Lansing | 3187 |
| Arbucklo | 3438 |

Set 5 1/2" casing at 3446'
w/100 sx com. Drilled plug
Swabbed to bottom
Filled up 100' muddy oil in
9 hr.
Acidized w/500 gal. Pressure
went from 900# to 1050# and
broke to 350#
Swabbed into tank 22 bbl oil
in 9 hr
Re-acidized w/1500 gal
Tested 5 BOPD, no wtr, 27
gravity oil
Temporary allowable 25 BOPD
effective 12-31-48
Pmpd. 7 1/2 bbl oil 52 1/2 bbl wtr
in 24 hr 5 bbl oil, 36 bbl
wtr in 24 hr 5 bbl oi, 35 bbl wtr
in 24 hr 20 bbl oil, 40 bbl wtr
in 24 hr.
Producing area 3446-3456

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1962
CONSERVATION DIVISION
Wichita, Kansas

5-15-62

State of Kansas



15-163-00223-00-00

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

WELL PLUGGING AUTHORITY

May 15, 1962

Well No. 1
Lease Griebel
Description NE NE NW 8-7-19W
County Rooks

Morgenstern & Specter Inc.
P. O. Box 661
Russell, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1962

CONSERVATION DIVISION
Wichita, Kansas

17-8-62

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J.P. Roberts

J. P. ROBERTS
Assistant Petroleum Conservation
Director

Mr. Eldon Petty Box 326 Hays, Kansas
is hereby assigned to supervise the plugging of the above named well.

In the event you need any further information regarding this well, feel free to write or call me at any time.

Harold J. Hollis
Kansas Field Supervisor
P. O. Box 85
Great Bend, Kansas
Phone: GL 3-2126