

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
30 South Market - Room 2078  
Wichita, Ks. 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-23,278 -00-00  
LEASE NAME RISELEY "B" #4  
WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1090 Ft. from <sup>N</sup> Section Line  
1440 Ft. from <sup>W</sup> Section Line  
SEC. 17 TWP. 7S RGE. 20 (E) or (W)

LEASE OPERATOR BAIRD OIL COMPANY  
ADDRESS P.O. BOX 428, LOGAN, KS 67646

COUNTY ROOKS

PHONE#( ) 913-689-7456 OPERATORS LICENSE NO. 5352

Date Well Completed 6-17-96

Character of Well D/A

Plugging Commenced 6-17-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-17-96

The plugging proposal was approved on 6-17-96 (date)

by HERB DINES (KCC District Agent's Name).

Is ACO-1 filled? Enclosed If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3707'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Fill with heavy mud. 1st plug from 3635'-3435' with 25 sks, 2nd plug from 1766'-1666' with 25 sks, 3rd plug from 1100'-700' with 100 sks, 4th plug from 315'-155' with 40 sks, 5th plug from 40'-0' with 10 sks, rathole 15 sks, total 215 sks.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Ste 801, Wichita, Ks. 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BAIRD OIL COMPANY

STATE OF Kansas COUNTY OF Sedgwick, 33. 8-27-96

Jim B. Baird (Employee of CONSERVATION DIVISION or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed th  
the same are true and correct, so help me God.

(Signature) Jim B. Baird  
(Address) Box 428 Logan KS 67646

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of August, 19 96

Robert B. Hartman  
Notary Public

My Commission Expires: 3/29/99

USE ONLY ONE SIDE OF EACH FORM

