

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

NOV 23 2005

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/15/05 (Date)

by: Rich Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) 3645-3652 Depth to Top: Bottom: T.D.

API Number: 15 - 147-97556-00 00874-00-00

Lease Name: Pinkerton

Well Number: #11

Spot Location (QQQQ): NE - NW - SW -

2310 Feet from North / South Section Line

4290 Feet from East / West Section Line

Sec. 29 Twp. 5 S. R. 20 East West

County: Phillips

Date Well Completed: 3/49

Plugging Commenced: 11/15/05

Plugging Completed: 11/15/05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

RU Swift Services. Hooked up to tbg. Pumped 300# hulls and 80 sx SMD cement @ 3602'. Circ 30 BO to wash pit. Pulled 58 jts tbg. Bottom of string @ 1804'. Pumped 300# hulls and mixed 95 sx SMD cement @ 1804'. Pulled remaining 58 jt tbg. Hooked up to 8 5/8" csg. Mixed 15 sx SMD cement. Pressured to 150 psi. SI @ 100 psi. Hooked up to 5 1/2" csg. Mixed 15 sx SMD cement. Pressured to 500 psi. SI @ 500 psi. Plug job complete 12:22 pm. Witnessed by Rich Williams w/KCC, Hays.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SWORN TO before me this 22nd day of November, 2005

Susan Brady My Commission Expires: 11-4-07 Notary Public

Bm