

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22350-00-00  
Spot: SENENW Sec/Twnshp/Rge: 34-31S-39W  
1027 feet from N Section Line, 2307 feet from W Section Line  
Lease Name: MLP CRAWFORD A Well #: 1-34  
County: STEVENS Total Vertical Depth: 5960 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5960	0	WITH 200 SX CMT
SURF	8.625	1808		WITH 610 SX CMT #193

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2005 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RANDY Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 25 SX CMT & 400# HULLS. CIRCULATE CMT TO SURFACE. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2005 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT WITH 400# HULLS. PUMP 50 BBL MUD & 100 SX CMT FROM 1830' TO 0'. PRESSURED TO 300#. PUMP 15 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURED TO 200#.

Perfs:


Top	Bot	Thru	Comments
5456	5463		

RECEIVED  
NOV 30 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

*Ken Jehlik*  
(TECHNICIAN)

INVOICED  
DATE 11-30-05  
INV. NO 2006060796