

11-3 4-032019

15-163-20153-00-02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1968

NE NW NW /4 SEC. 19, 07 S, 19 W
4950 feet from S section line
4290 feet from E section line

Operator license# 5352 Lease Collins Heirs well # 1

Operator: Baird Oil Company, Inc. County Rooks

Address: Box 428 Well total depth 3453 feet 112.22
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 3 Month: November Year: 94

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: _____

Were: Order 150 sxs. 60/40 pozmix - 10% gel - 300# hulls - 15 sxs. gel.
Allied Cement Company.

RECEIVED
KANSAS CORPORATION COMMISSION
11-10-1994
NOV 10 1994

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 9:00A.M., Day: 3, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 206' w/115 sxs. cwc. 5 1/2" set @
3453' w/100 sxs. plus D.V. tool set @ 1438' cwc. w/350 sxs. Critical
area control shot at 2100' (salt gel). Squeezed 5 1/2" w/25 sxs. cement
blend, followed by 15 sxs. gel, followed by 125 sxs. cement blend w/300#
hulls mixed in to Max. P.S.I. 800#. Close in P.S.I. 300#. 8 5/8" tested
to 300# cement at surface. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did observe the plugging. Carl Goodrow

INVOICED

100

(agent)

Form CP-2/3

DATE 11-29-94

INV. NO. 41741