

4-031955

7-26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,079-00-00

SW NW SE /4 SEC. 18, 07 S, 19 W  
1140 feet from S section line  
1940 feet from E section line

Operator license# 5352

Lease Ross Heirs well # 3

Operator: Baird Oil Company, Inc.

County Rooks

113.32

Address: Box 428  
Logan, Kansas 67646

Well total depth 3487 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 273 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 26 Month: July Year: 94

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:                     

Were: Order 150 sxs. 60/40 pozmix - 10% gel - 200# hulls - 8 sxs. gel

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 05 1994  
08 05-1994  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:00A.M., Day: 26, Month: July, Year: 94

Actual plugging report: 8 5/8" set @ 273' w/175 sxs. 4 1/2" set @ 3481'  
w/240 sxs. O.H. 3512' - D.V. at 1550' cwc. Squeezed 4 1/2" w/25 sxs.  
cement blend w/200# hulls followed with 8 sxs. gel followed with 100 sxs.  
cement blend to Max. P.S.I. 1500#. Close in P.S.I. 1500#. Test  
8 5/8" annulus to 400# with 10 sxs. cement blend. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:                      GL

I did X / did not     observe the plugging. Carl Goodrow

INVOICED

DATE AUG 11 1994

INV. NO. 40933

(agent)

Form CP-2/3