

4-032335

11-25

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,830-00-00

NE NE SW _____ /4 SEC. 18, 07, 19 W
2310 _____ feet from S section line
2970 _____ feet from E section line

Operator license# 5352

Lease: Culp (Rose) Well # 3

Operator: Baird Oil Company, Inc.

County: Rooks 113.49

Address: P.O. Box 428
Logan, Kansas 67646

Well total depth 3492 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 25 Month: November Year: 1998

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: -

Were: Order 280 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 9:45 A.M., Day: 25 Month: November Year: 1998

Actual plugging report: 8 5/8" set at 248' w/190 sxs cwc. 5 1/2" set at 3485' w/125 sxs.
Prod. Perfs 3402' - 3406'. D.V. at 1571' w/400 sxs cwc. Squeezed 5 1/2" with 240 sxs cement
blend with 500# hulls mixed into Max. P.S.I. 900#. S.I.P. 400#.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____

Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

12-09-1998
8661

10

DEC 15 1998

60427


REPLACEMENT CARD

BAIRD OIL COMPANY
 BOX 428
 LOGAN, KS. 67646
 #3 ROSE CULP
 18-7-19W
 2240'ESI &
 2240'FWL, SW/4

CONTR ABERCROMBIE DRILLING CTY ROOKS

GEOL JIM BAIRD FIELD VALLEY VIEW

ELV 2037 KB SPD 11/22/85 CARD ISSUED 3/6/86 IP P 8 BO & 4 BWPD
 2032 GL DRLG COMP 11/27/85 LKC 3402-3406
 API 15-163-22,830



LOG	Tops	Depth/Datum
*ANH	1565 +	472
*B/ANH	1597 +	440
TOP	2991-	954
HEEB	3192-	1155
TOR	3215-	1178
LANS	3231-	1194
STARK	3350-	1313
BKC	3436-	1399
ARB	3482-	1445
LTD&RTD	3492-	1455
*SAMPLE TOPS		

8 5/8 " 248 / 190 SX, 5 1/2 " 3485 / 40 SX
 NO CORES
 DST (1) 3374-3400 (LKC) / 45-45-30-45, REC 5' DM, SIP 0-0#,
 FP 62-62 / 0-0#
 DST (2) 3391-3418 (LKC) / 45-45-30-45, REC 10' SLI OCM, W /
 SHOW FREE OIL IN TOOL, SIP 76-57#, FP 48-48 / 48-48#, BHT
 104"
 DST (3) 3479-3492 (ARB) / 45-45-45-45, REC 155' CLEAN GSY
 OIL, 10' MCO, SIP 758-695#, FP 10-31 / 41-51#
 MICT - CO, PF (KC) 3402-3406, W / 4 SPF, AC 250 GAL (28%) &
 1500 GAL (15%) & 6 BBL OVERFLUSH, SWB DWN, SO, POP, P 8
 BO & 4 BWPD, 12/18/85

INFO RELEASED: 3/26/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS