

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,148-00-00

*SE (DSS 6-9-05)*

NE NW NE /4 SEC. 18, 07 S, 19 W  
2310 feet from S section line  
1550 feet from E section line

Operator license# 5352

Lease Ross Heirs well # 2

Operator: Baird Oil Company, Inc.

County Rooks

Address: Box 428  
Logan, Kansas 67646

Well total depth 3479 feet *113.06*  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 210 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License#    

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 26 Month: July Year: 94

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:    

Were: Order 150 sxs. 60/40 pozmix - 10% gel - 200# hulls - 11sxs. gel.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:15A.M., Day: 26, Month: July, Year: 94

Actual plugging report: 8 5/8" set @ 210' w/110 sxs. 5 1/2" set @ 3473'  
w/100 sxs. D.V. tool set at 1502' w/375 sxs. cwc. Perf. 3372' - 3382'.  
Squeezed 5 1/2" w/25 sxs. cement blend w/200# hulls mixed in followed  
w/11 sxs. gel followed w/125 sxs. cement blend to Max. P.S.I. 700#.  
Close in P.S.I. 500#. Test 8 5/8" annulus to 500# cement at surface.  
Plug complete.

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

AUG 05 1994  
08-05-1994  
CONSERVATION DIVISION  
WICHITA, KS

I did X did not     observe the plugging. Carl Goodrow

DATE AUG 11 1994

(agent)

INV. NO. 40932