

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20077-00-06⁰¹
Spot: SWSWNE Sec/Twnshp/Rge: 18-7S-19W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ROSS HEIRS Well Number: 1
County: ROOKS Total Vertical Depth: 3498 feet

Operator License No.: 5352

Conductor Pipe: Size feet:

Op Name: BAIRD OIL CO, INC

Surface Casing: Size 8.625 feet: 206 125 SX CMT

Address: BOX 428 MAIN STREET
LOGAN, KS 67646

Production: Size 5.5 feet: 3490 475 SX CMT

Liner: Size feet:

12/28

113.69

Well Type: SWD

UIC Docket No: D17471.0

Date/Time to Plug: 12/28/2000 8:00 AM

Plug Co. License No.: 5352

Plug Co. Name: BAIRD OIL CO, INC

Proposal Rcvd. from: JIM R. BAIRD

Company: BAIRD OIL CO, INC

Phone: (785) 689-7456

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/28/2000 11:00 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 206' w/125 sxs cwc. 5 1/2" set at 3490' w/475 sxs.
PBTD 1354'. Prod. Perfs 1150' - 1200'.
D.V. at 1354' w/375 sxs cwc.
Squeezed 5 1/2" with 200 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1200#. Held.
Squeezed 8 5/8" to test - would not take at 1200# P.S.I.

KCC

JAN 08 2001
RECEIVED
KANSAS CORPORATION COMMISSION
HAYS, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

JAN 10 2001
01-10-2001
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

DATE 1/10/01

NO. 2001061256

Form CP-2/3

JAN 03 2001

NATIONAL ASSOCIATED PETR CO. #1 ROSS HEIRS 18-7-19W
SW SW NE

Contr. THOROUGHbred DRLG Cty. ROOKS
Geol. JOE MCGARRAH Pool VALLEY VIEW DISC
E. 2038 KB Cm. 11/6/67 Cp. 1/11/68 IP 35 BOPD + 85%W
ARB 3489-3500

API 15-163-20,077

SMP Tops	Depth	Datum
ANHY	1560	+ 478
TOP	2996	- 958
HEEB	3196	-1158
TOR	3320	-1182
LANS	3236	-1198
BKC	3448	-1410
ARB	3488	-1450
LTD	3498	-1460
RTD	3500	-1462

Csg. 8" 206/125 SX, 5" 3489
DST 3144-78/1', 120' MD, BHP 1197-1172#/30", FP 36-112#
DST 3184-3228/1', 60' WTR GCM, BHP 1150-1071#/30", FP 56-80#
DST 3280-3325/1', 260' MW, S/OIL BHP 1205-1086#/30", FP 72-176#
DST 3492-3500/1', 30' GSY OIL, 120' CL OIL, 30' MCO, BHP 984-864#/30", FP 32-72#
D CEM & CO TO 3500' TD, FU 500' OIL, 50 GALS, SWB 1/2 BOPD, NW, GRAV 24, FU 3200'/48' HRS, A 500, SWB 28 BO & 28 BOPD, POP, PMP 20 OIL & 70 WTR/12 HRS, PMP 20 BO + 65 TO 70 WTR,

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS