

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23448-00-00
Spot: NWNENW Sec/Twnshp/Rge: 21-14S-19W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KRAUS TWIN Well #: 4
County: ELLIS Total Vertical Depth: 3850 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		3824		
PROD	5.5	3855	0	125 SX CMT
SURF	8.625	200	0	125 SX CMT

13
A/125

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2005 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement - 1500# hulls.
Fluid Level 300'.
No squeeze records. Perforate one hole at 2125' - 1475' - 750'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2005 4:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated one hole at 2125' - 1475' - 750'.
Ran tubing to 2091'. Swift Services pumped 130 sxs Swift Multi-Density cement with 600# hulls - no circulation.
Pulled tubing to 1160'. Swift Services pumped 70 sxs SMD with 375# hulls - no circulation.
Pulled tubing to 584'. Swift Services pumped 70 sxs SMD with 375# hulls - cement circulated. PTOH. Squeezed with 30 sxs SMD.
Max. P.S.I. 50#. Casing full.
Hooked up to backside instant 600#.
Note: Left tubing, anchor and one joint 2 7/8" tubing at 3740'

Perfs:

Top	Bot	Thru	Comments
3850	3855	OH	
3786	3855		

RECEIVED
DEC 07 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-8-05
INV. NO. 2006060812

DEC 06 2005

replacement card

WEILERT ENTERPRISES
HAYS KS

4 KRAUS D. DONALD TWIN

21-14S-19W
100'NW, 6-1/4'NW-NW

site: 2-3/4 N & 2-1/4 W OF ANTONIO KS

city: ELLIS

API 15-051-23448

contr: HELBERG OIL CO

field: KRAUS

well:

fr date 05/09/83

spc date 05/25/83

drig comp 05/31/83

card issued 10/27/83

last revised 08/09/99

+			

ELV: NA

tops.....depth/datum

RTD.....3850

NO TOPS RPTD

IP status:

D & A, ARB, 10/20/83

INFO RELEASED: 8/9/99 - WAS TEMP ABD

CSG: 8-5/8" 200+, 4-1/2" 3850

COMMENT: EXACT WELL FTG LOC IS UNKNOWN
NO CORES OR DSTS

TRGT ZN: ARB (OIL), PTD 3850 (ARB), MICT - CO, PF

(ARB) INTV NA, SWB DWN, SLI SO, SI - EVAL

(9/15/83), TEMP ABD (10/20/83), NON-COMMERCIAL,

WELL NEVER PRODUCED; NO PROD HISTORY; CHGD

STATUS TO D & A (DATE NA) - NO OTHER INFO

RELEASED BY OPERATOR OR ON KCC RECORDS (NO

ACO); ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1999
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INNOVATION

WELL LOG