

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15604-00-00
Spot: NWNENW Sec/Twnshp/Rge: 25-20S-12W
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: JACKSON Well #: 1
County: BARTON Total Vertical Depth: 3349 feet

Operator License No.: 31199
Op Name: JOINER, DON DBA D J OIL OPERATION
Address: 305 E. 6TH
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3301		
PROD	5.5	3347	0	UNKNOWN
SURF	8.625	260	0	UNKNOWN

#108 84

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DON JOINER Company: JOINER, DON DBA DJ OIL OPERAT Phone: (620) 792-9416

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 10/31/2005 2:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 575' and 1425'.
Ran tubing to 2000'.
Pumped 200 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Pulled to 1200'.
Circulated with 150 sxs cement and 200# hulls.
POOH.
Pumped 20 sxs cement down casing.
Max. P.S.I. 500#. S.I.P. 400#.
Pumped 100 sxs cement down backside.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3312	3316		
3272	3277		
3258	3263		
3186	3191		
323	342		

RECEIVED
DEC 07 2005
KCC WICHITA

Remarks: COPELAND CEMENT COMPANY.

Plugged through: CSG

District: 04

(Signature)

Signed _____

(TECHNICIAN)

INVOICED

DATE 12-8-05

INV. NO. 2006040818

NOV 23 2005

ALPINE OIL & ROYALTY

#1

JACKSON

AA

25-20-12W
NW NE NW

53

Contr.

BARTON

County

E 1819

Comm.

Comp.

11-19-48

IP


3000 BOPD

Tops	Depth	Datum
HEEB	2969	-1156
BR LIME	3097	-1278
LANS	3115	-1296
ARB	3345	-1526
T.D.	3355	-1536

Casing

5" 3347

2800' 01H/10 HRS
SWB 65 BOPH/5 HRS



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WICHITA

WICHITA

WICHITA