

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21737-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 23-11S-22W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HILLMAN B Well #: 4
County: TREGO Total Vertical Depth: 4000 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3998	0	425 SX CMT
SURF	8.625	259	0	170 SX CMT

130⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2005 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Production casing cemented bottom to surface.
Fluid level 300'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2005 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2423'. Allied pumped 150 sxs 60/40 pozmix - 10% gel with 300# hulls cwc.
PTOH. Squeezed with 50 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 400#.
Hooked up to backside and pumped 10 sxs cement with 150# hulls.
Blew hole below head.

Perfs:

Top	Bot	Thru	Comments
3867	3879		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-8-05

INV. NO. 2006060821

DEC 02 2005

STRATA ENERGY
RESOURCES CORPORATION
4101 BIRCH ST., #130

REPLACEMENT CARD

23-11-22W
NW NW SW


#4 HILLMAN

NEWPORT BEACH, CA 92660
CONTR RED TIGER DRILLING

CTY TREGO

GEOLOGICAL BOB WILSON

FIELD GAGELMAN SQ. EXT
(1/8 S)



ELV 2274 KB SPD 6/22/85 CARD ISSUED 12/5/85
2267 GL DRLG COMP 6/30/85
API 15-195-21,737

IP P 30 BO & 2 BWPD
MARM 3867-3879

LOG	Tops	Depth/Datum
ANH		1728+ 546
TOP		3331-1057
HEEB		3512-1238
TOR		3536-1262
LANS		3551-1277
BKC		3788-1514
MARM		3860-1586
CONG		3896-1622
ARB		3969-1695
RTD		4000-1726

8 5/8 " 259 / 170 SX, 4 1/2 " 3998 / 425 SX
NO CORES

DST (1) 3706-3717 (LKC) / 30-30-30-30, REC 5' DM, SIP 32-32#, IFP 32# / FFP 32#, HP 1961-1039#, BHT 110°
DST (2) 3864-3882 (MARM) / 30-45-45-45, 750' GIP, REC 690' CLEAN GSY OIL, 180' MCO, SIP 1135-1016#, FP 173-239 / 176-326#, HP 2047-2014#, BHT 116°
MICT - CO, PF (MARM) 3867-3879, W / 2 SPF, AC 1250 GAL (7.5% DSFE) & 25 BALL SEALERS & 5500 GAL GEL PAD & 2% KCLW (AMT NA), SWB DWN, SO, POP, P 30 BO & 2 BWPD, 7/24/85

INFO RELEASED: 11/27/86 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WILSON