

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21822-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 23-11S-22W  
1650 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HILLMAN Well #: 6  
County: TREGO Total Vertical Depth: 3950 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3946	0	440 SX CMT
SURF	8.625	260	0	170 SX CMT

*#128 38*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2005 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid level 300'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2005 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2423'. Allied pumped 120 sxs 60/40 pozmix - 10% gel with 300# hulls cwc.  
PTOH. Squeezed with 65 sxs cement with 150# hulls.  
Max. P.S.I. 1400#. S.I.P. 1000#.  
Hooked up to backside - pumped 5 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Note: 4 1/2" cemented bottom to surface - 440 sxs.

Perfs:

Top	Bot	Thru	Comments
3858	3868		

RECEIVED  
DEC 07 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 12-8-05

INV. NO. 2006060821

Form CP-2/3


DEC 02 2005

replacement card  
 STRATA ENERGY RESOURCES CORPORATION  
 NEWPORT BEACH, CA. 92660

23-11 -22W  
 SE NW SW

#6 HILLMAN

site: 2-3/4 N & 7-1/4 E OF WAKEENEY, KS      city: TREGO      API 15-195-21822  
 contr: RED TIGER DRILLING      field: GAGELMAN SO.  
 geol: GOOLSBY BROS.  
 fr      spd      drig      card      last  
 date 11/18/85      date 11/18/85      comp 11/25/85      issued 07/31/86      revised 06/03/87



ELV: 2254 KB LOG  
 tops .....depth/datum  
 ANH.....1698 +556  
 B/ANH.....1748 +506  
 TOP.....3287 -1033  
 HEEB.....3498 -1244  
 TOR.....3523 -1269  
 LANS.....3638 -1384  
 BKC.....3769 -1515  
 MARM.....3850 -1596  
 CONG.....3885 -1631  
 RTD.....3950 -1696

**IP status:**

**OIL, P 30 BO & 5 BWPD, MARM 3858-3868 ,**  
 CSG: 8-5/8" 259.86 / 170 SX, 4-1/2" 3946 / 440 SX  
 NO CORES  
 DST (1) 3857-3876 (MARM), / 45-45-45-45, 300' GIP, REC  
 120' HO & GCM, 120' GSY MDY OIL, 60' CLEAN OIL ISIP  
 947# FSIP 846# IFP 61# -89# FFP 123# -132# IHP 2111#  
 FHP 2107# BHT 119 °  
 MICT - CO, PF (MARM) 3858-3868, W / 2 SPF, AC 1500  
 GAL & 20 BALL SEALERS, GSO, SET 2-3/8" TBG (DEPTH  
 NA), POP, P 30 BO & 5 BWPD (GR 38), 1/28/86

INFO RELEASED: 6/3/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS