

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20763-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 16-10S-26W  
2290 feet from N Section Line, 2280 feet from W Section Line  
Lease Name: TILTON Well #: 16-6  
County: SHERIDAN Total Vertical Depth: 4450 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 155 N. MARKET, STE 1010  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4450	0	265 SX CMT
SURF	8.625	303	0	200 SX CMT

# 144<sup>63</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2005 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1559

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2005 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 303' w/200 sxs cement.  
4 1/2" production casing set at 4450' w/265 sxs cement.  
Multiport stage collar set at 2233' w/475 sxs cement. TD 4450'.  
Connected to 4 1/2" production casing - pumped 200 sxs cement with 500# hulls.  
Max. P.S.I. 1000#. S.I.P. 900#.  
Connected to 8 5/8" surface casing - pumped 1/2 sack cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4017	4020		
3896	3898		
3856	3859		
3843	3846		

RECEIVED  
DEC 05 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #21701.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

NOV 22 2005

INVOICED  
DATE 12-8-05  
NO. 2006060835

INDEXED

L. B. PETROLEUM, INC. REPLACEMENT CARD  
 110-16TH ST., #800 #16-6 TILTON  
 DENVER, CO 80202 16-10-26W  
 CONTR WARRIOR DRILLING, INC. 2290' FNL &  
 CTY SHERIDAN 2280' FWL, NW/4  
 GEOL MICK DOMENICK FIELD FULLER SO. EXT (1/BN)  
 ELV 2570 KB SPD 8/24/84 CARD ISSUED 10/25/84 IP P 153 BO & 23 BWPD  
 2565 GL DRLG COMP 9/1/84 LKC(SWOPE) 4017-4020  
 API 15-179-20,763

+	+
+	+
+	+
+	+

SMP	Top	Depth/Datum
SC	2201+	369
HEEB	3784	1214
35' ZN	3850	1280
MUN CR	3944	1374
DENNIS	4002	1432
STARK	4010	1440
B/LANS	4054	1484
ALT	4108	1538
RTD	4450	1880

8 5/8 " 303 / 200SX, 4 1/2 " 4450 / 265SX, MULTI STAGE COL-  
 LAR AT 2233 / 475SX  
 DST (1) 3838-3858 (LANS) / 30-45-45-60, 750' GIP, REC NA,  
 PRESSURES NA  
 MICT - CO, PF (SWOPE) 4017-4020, W / 2 SPF, AC 150 GAL  
 (15% MA), GSO, SET 2 3/8 " TBG AT 4066', POP, P 153 BO &  
 23 BWPD (GR 29.3"), 9/12/84

INFO RELEASED: 3/6/86 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS