

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21827-00-01
Spot: SENWNW Sec/Twnshp/Rge: 23-11S-22W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HILLMAN B Well #: 7
County: TREGO Total Vertical Depth: 3934 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3933	0	440 SX CMT
SURF	8.625	262	0	175 SX CMT

#12786

Well Type: EOR UIC Docket No: E27129.1 Date/Time to Plug: 11/23/2005 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perforated 1100' w/175 sxs cwc.
Squeeze jobs: 3328'-3362' w/200 sxs; 3069'-3102' w/200 sxs; 2943'-2974' w/150 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2005 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2554'. Allied pumped 125 sxs 60/40 pozmix - 10% gel with 400# hulls cwc.
PTOH. Squeezed with 125 sxs cement with 100# hulls.
Max. P.S.I. 1300#. S.I.P. 900#.
Hooked up to backside and pumped 10 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3842	3852		

RECEIVED
DEC 05 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

110

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-8-05
INV. NO. 2006060833

Form CP-2/3

NOV 23 2005

replacement card
 STRATA ENERGY RESOURCES CORPORATION
 NEWPORT BEACH, CA. 92660

23-11 -22W
 SE NW NW

#7 HILLMAN

site: 3-1/4 N & 7-1/4 E OF WAKEENEY, KS

city: TREGO


API 15-195-21827

contr: RED TIGER DRILLING

field: GAGLEMAN SO.

geol: GOOLSBY BROS.

fr	spd	drig	card	last
date 12/05/85	date 12/07/85	comp 12/14/85	issued 07/31/86	revised 06/03/87



ELV: 2236 KB LOG	
tops	depth/datum
ANH	1682 +554
B/ANH	1734 +502
TOP	3271 -1035
HEEB	3487 -1251
TOR	3510 -1274
LANS	3525 -1289
BKC	3756 -1520
MARM	3842 -1606
CONG	3866 -1630
ARB	3929 -1693
RTD	3934 -1698

IP status:

OIL, P 60 BOPD, MARM 3842-4852,
 CSG: 8-5/8" 262 / 170 SX, 4-1/2" 3933 / 440 SX, MULTI
 STAGE COLLAR AT 3838
 NO CORES
 DST (1) 3836-3856 (MARM), / 45-45-45-45, 248' GIP, REC
 144' CLEAN FREE OIL ISIP 1161# FSIP 1114# IFP 95#
 -202# IHP 2031# FHP 2026#
 MICT - CO, PF (MARM) 3842-3852, W / 2 SPF, AC 1500
 GAL & 20 BALL SEALERS, SET 2-3/8" TBG (DEPTH NA),
 POP, P 60 BOPD (GR 36), 4/1/86

INFO RELEASED: 6/3/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

INDEXED