

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20541-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 25-13S-30W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BECK Well #: 2
County: GOVE Total Vertical Depth: 4720 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4214	0	140 SX CMT
SURF	8.625	190	0	150 SX CMT

40
#153

Well Type: SWD UIC Docket No: D20465.0 Date/Time to Plug: 11/21/2005 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION, INC. Phone: (785) 483-1559

Proposed Plugging Method: Ordered 165 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2005 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 190' w/150 sxs cement.
5 1/2" production casing set at 4214' w/140 sxs cement
Well plugged on August 3, 1959 - 1100' of 5 1/2" production casing pulled from the well.
Re-entered October 19, 1981 - washed down - re-ran 5 1/2" casing to 1100'.
Set 4 1/2" production casing at 2100' with 250 sxs cement.
Perforations at 1990' - 2048'.
Connected to 4 1/2" casing - pumped 150 sxs cement with 500# hulls.
Max. P.S.I. 1100#. S.I.P. 700#.
Connected to 8 5/8" surface casing - pumped zero sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
2000	2054		

RECEIVED
DEC 05 2005
KCC WICHITA

Remarks: LEASE FORMERLY KNOWN AS ADA L. MOORE #1. ALLIED CEMENTING COMPANY-TICKET #21700.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 12-8-05
INV. NO 2006060828

Form CP-2/3

NOV 22 2005

THE DANE G HANSEN TRUST
 P.O. BOX 187 #2 BECK "OWWO" 25-13-30W
 LOGAN, KS 67646 NW NW NW
 CONTR POE WELL SERVICE INC CTY GOVE

GEOL _____ FIELD GOVE

E 2877 KB CM 10/19/81 CARD ISSUED 5/27/82 IP SWDW

+	+	+
+	+	+
+	+	+

API 15-063-20,541-A CED HILL 2000-2054

LOG	TOPS	DEPTH	DATUM
ANH		2300	+ 577
B ANH		2330	+ 547
HEEB		3880	-1003
TOR		3902	-1025
KC		3916	-1039
BKC		4212	-1335
MARM		4232	-1355
FT SC		4394	-1517
CHER		4424	-1547
MISS		4492	-1615
VIO		4644	-1767
ARB		4685	-1808
TD		4720	-1843

OLD INFO: OPERATOR WAS O A SUTTON, #1
 ADA L MOORE, SPD NA, SET E 8-5/8" 190,
 5" 4214, COMP AS P 153 BOPO KC 4122-32,
 1/24/54 CONTR LEWIS DRLG

DST (1) 3919-31, OP 60", REC 70'WM,
 SIP 102#, FP NA
 DST (2) 4005-25, OP 30", REC 210'W, SIP
 1170#, FP NA
 DST (3) 4119-33, OP 60", 3020'GIP, REC
 450'0, 50' MDY 0, SIP 1160#, FP NA
 DST (4) 4493-4500, OP 60", REC 5'M,
 SIP 0#, FP NA
 MICT - CO. PF (KC) 4122-30, SWB 4 1/2 BOPH

/2 HRS, PF (KC) 24/4126-32, SWB 3/4 BOPH, AC 2000G, SWB 2 BOPH,
 POP, P 153 BOPD, KC 4122-32

CORRECTED ELEV 3/9/56

NEW INFO: RE-ENTERED 10/19/81, WSH DWN, SET 4 1/2" 2100',
 MICT - CO, PF (CED HILL) 2000-2054, SWDW - INJECTION RATE
 SATISFACTORY