

To: 6 040990
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-8
API NUMBER 15-1103-01316-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis Corp
Name & Address: Box 247
Wichita, Ks. 67201

NW NW NW, SEC. 9, T 7 S, R 19 W/E
feet from S section line
feet from E section line

Lease Name Riffe Unit 4-3
Desmarceau Well # 3
County Rooks 113.00

Total Depth 3477 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 179' w/130

Abandoned Oil Well Gas Well _____ Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____
Wichita, Kansas

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 8 Month: Dec Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Graham Michaelis Co. (phone) _____

were: 5 1/2" casing set at 3472' w/125 sks. Top perf at 3176'.

Perf anhy at 1570' and base dakota at 875'. 4 1/2" liner to 3087' circ w/300 sks cement.

Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/4 F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 8 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 175 sks cement w/1/4

F.C. plus 4 sks Hulls mixed in cement. Max 800# S.I. 500# psi. Pumped in 8 5/8"

75 sks cement w/1/4# F.C. plus 1 sk Hulls mixed in cement. Max 600# S.I. 300# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 1-19-89

INV. NO. 23697

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel