

6 070791

J 8-25

163-23,055-06-00 277 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
4950 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140  
Operator: Frontier Oil Co.  
Name & Address: 125 N. Market #1720  
Wichita, Ks. 67202  
George Angle

Lease Name Dryden Well # 1  
County Rooks 113.85  
Well Total Depth 3503 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number 5140 5302

Address 125 N. Market #1720 Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 23 Month: August Year: 19 89

Plugging proposal received from W. C. Ogel

(company name) Frontier Oil Company (phone) 316-263-1201

were: 8 5/8" 220' s.p. cwc w/140 sks 60/40 poz 2% gel 3% ca cl By Allied.  
Arbuckle at 3450'; Elev. 2000'; Anhy 1525'; Proposal 215 sks 60/40 pzo 6% gel

3% cal. Cl and 8 5/8" plug. Spot with drill stem. Circulate heavy mud between plugs.  
No cir problems. Vis 48 Weight 9.3 water loss 9.8.25 sks at 3390' 25 sks at 1535'.

100 sks w/1 f.c. at 900' 40 sks at 270'. 10 sks plug at 40'. 15 sks rathole (circulate).

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:45AM Day: 25 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Frontier ordered 215 sks 60/40 poz 6% gel 3% cal cl and 8 5/8" plug. Spot with drill stem, circulate heavy mud between all plugs.

1st plug at 3390' w/25 sks cement. 2nd plug at 1535' w/25 sks cement.

3rd plug at 900' w/100 sks cement w/1 sk f.c. 4th plug at 270' w/40 sks cement.

10 sks at 40' 15 sks in rathole (circulate) By Allied Cement

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I, ~~xxxxx~~ did not observe this plugging.

INVOICED

DATE 9-11-89

INV. NO. 25861 8-25

Signed *Marion J. Schmidt* Part IV (TECHNICIAN) Marion J. Schmidt

RECEIVED STATE CORPORATION COMMISSION

SEP - 6 1989

9-6-89