

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00230-00-01
Spot: SESENE Sec/Twnshp/Rge: 4-9S-18W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: LOVE Well #: 4
County: ROOKS Total Vertical Depth: 1575 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.38	207		

#51¹⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/02/2005 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: CHARLIE RAMSEY Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 200# hulls.
Anhy: 1411' - 1441'.
7" casing set at 3509'. Pulled casing at 1216'-1220' and plugged well.
Drilled cement from 0'- 714'. Unable to get below 1575'. Bad casing.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2005 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1192'. Allied pumped 25 sxs cement with 100# hulls.
Pulled tubing to 820'. Allied pumped 75 sxs cement with 200# hulls.
Pulled tubing to 257'. Allied pumped 45 sxs cement with 100# hulls - cement circulated.
PTOH. Topped with 5 sxs cement - hole full.
Note: Heavy drilling mud between all plugs.

Perfs:

RECEIVED
DEC 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICE

DATE

12-8-05

INV. NO.

2006060814

Form CP-2/3

DEC 02 2005