

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21984-00-00

Spot: SWSWNW

Sec/Twnshp/Rge: 35-28S-8W

3093 feet from S Section Line,

4660 feet from E Section Line

Lease Name: RAMSEY

Well #: 3

County: KINGMAN

Total Vertical Depth: 4260 feet

Operator License No.: 5254

Op Name: MIDCO EXPLORATION, INC.

Address: 414 PLAZA DRIVE #204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4090		
PROD	4.5	4242		190 SX CMT
SURF	8.625	252		250 SX CMT

\$138⁴⁵

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/22/2005 1:00 PM

Plug Co. License No.: 30891

Plug Co. Name: LEIKER WELL SERVICE, INC.

Proposal Rcvd. from: DAVID MAYFIELD

Company: MIDCO EXPLORATION, INC.

Phone: (620) 786-9166

Proposed
Plugging
Method:

SET CIBP @ 4090', CUT CSG AS DEEP AS POSSIBLE, 35 SX @ 1250', 35 SX @ 750', FILL TO SURFACE FROM 300' - VERBALLY APPROVED BY STEVE.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/22/2005 5:00 PM

KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

CIBP at 4090' with 25 sacks of cement on plug. Shot and pulled casing to 1250' and spotted 35 sacks of cement. Pulled to 750' and spotted 35 sacks of cement. Pulled to 300' and circulated cement to surface with 85 sacks of cement.

60/40 posmix with 4% gel

Allied #20992

Perfs:

Top	Bot	Thru	Comments
4112	4116		

**RECEIVED
KCC DISTRICT #2
NOV 23 2005
WICHITA, KS**

**RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 2005**

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

INVOICED
DATE 12.8.05
INV. NO. 2006060820