

15-163-01313-00-00 12-8

To: 6 040993
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A 1959

NE NE NE, SEC. 8, T 7 S, R 19 W/E

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Riffe Unit 3-1 Well # 1
Dryden

Operator: Graham Michaelis Corp
Name & Address: Box 247
Wichita, Ks. 67201

County Rooks 112.65

Well Total Depth 3466 feet

Conductor Pipe: Size _____ feet

Casing: Size 8 5/8 feet 323 w/185

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Ressel, Ks.

Company to plug at: Hour: 8:00AM Day: 8 Month: Dec Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Graham Michaelis (phone) _____

were: 5 1/2" casing set at 3452' w/60 sks. Top perf at 3177'. Perf anyh at 1570'

and base dakota at 875'. (3 holes) 4 1/2" welded liner to 3147' circ w/200 sks cement.

Ordered 225 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15AM Day: 8 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 125sks cement w/1/4# F.C. plus 4 sks Hulls mixed in cement. Max 1000# S.I. 900# psi. Pumped in 8 5/8" casing 75 sks cement w/1/4# F.C. plus 1 sk Hulls mixed in cmeent. Max 700# S.I. 300# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 1-19-89

INV. NO. 23695

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel