

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis Corp
Name & Address: Box 247
Wichita, Ks. 67201

API NUMBER 15- NA E-16, 341

NW NW NE, SEC. 8, T 7 S, R 19 W/EX

feet from S section line

feet from E section line

Lease Name Riffe 3-2-I
Dryden Well # 2

County Rooks 111.87

Well Total Depth 3442 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 309' w/275

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: 8:30AM Day: 9 Month: Dec Year: 19 88

Plugging proposal received from Norman Rodie

(company name) GMC (phone)

were: 7" casing set at 3426' w/75 sks. Top perf at 3154'. Perf anhy at 1570' and

base dakota at 875'. 4 1/2" liner cemented to surface w/450 sks.

RECEIVED
STATE CORPORATION COMMISSION

1-18-89

18 1989

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15PM Day: 9 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 150 sks cement w/1/4# F.C. plus 4 sks Hulls.
mixed in cement. Max 700#. S.I. 400# psi. Pressured up annulus 1500#. (Black Magic)

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

DATE 1-19-89

INV. NO. 23694