

15-163-03900-00-8801 72-8

To: 6 040992
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A 1959
NW ~~SW~~ NE, SEC. 8, T. 7 S, R19 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134 Lease Name Riffe Unit 3-35 Dryden B Well # 1

Operator: Graham Michaelis Corp RECEIVED
Name & Address Box 247 STATE CORPORATION COMMISSION
Wichita, Ks. 67201 Rooks 111.96
Well Total Depth 3445' P.B. at 1004' set
Conductor Pipe: Size _____ feet

JAN 18 1989
1-18-89
CONSERVATION DIVISION
Wichita, Kansas

Abandoned Oil Well _____ Gas Well _____
Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____ Supply Well _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 8 Month: Dec Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Graham Michaelis (phone) _____

were: 7" casing set at 3443' w/75 sks. Top perf at 952'. B.P. at 3150'. Sanded to 1004' - 4 1/2" liner cemented at 1004' to surface w/180 sks. Holes in 7" - 700'.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 8 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 40 sks cement plus pumped in 4 1/2" casing

35 sks cement w/1/4" F.C. plus 3 sks Hulls mixed in cement. Max 1100# S.I. 1000# psi.

Pumped in 10 3/4" casing 150 sks cement w/1/4" F.C. plus 2 sks Hulls mixed in cement.

Max 600# S.I. 400# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-19-89

INV. NO. 23690

Signed Dennis L. Hamel (TECHNICIAN)