

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-19125-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 29-5S-20W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: PINKERTON A Well #: 9  
County: PHILLIPS Total Vertical Depth: 3632 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3619	0	w/100 sxs cmt
SURF	8.625	154	0	w/125 sxs cmt

04  
\$118

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2005 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8036

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement and 500# hulls.  
PBTB 3615'. Deep casing leak.  
No records of squeeze jobs. Perforate at 1150' and 1800'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/14/2005 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated one hole at 1800' and 1150'.  
Ran 2 3/8" tubing to 3602'.  
Swift Services pumped 80 sxs Swift Multi-Density Cement with 300# hulls - good circulation.  
Pulled tubing to 1850'. Swift pumped 95 sxs SMD with 375# hulls - circulated cement.  
PTOH. Squeezed with 15 sxs SMD.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside - pumped 10 sxs SMD.  
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3602	3608		

RECEIVED  
DEC 05 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 12-8-05

INV. NO. 2006060833

Form CP-2/3

DEC 01 2005