

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24396-00-00  
Spot: SW Sec/Twnshp/Rge: 14-18S-26W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: LAMOREE Well #: V1-14  
County: NESS Total Vertical Depth: 4580 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: PO BOX 116  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	383	0	

#148<sup>85</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/11/2005 8:00 AM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: SKIP SMITH Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 1930' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 410' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 11/11/2005 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1930' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 410' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.


Perfs:

RECEIVED  
DEC 05 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Eric MacLaren

(TECHNICIAN)

INVOICED

DATE 12-8-05  
INV. NO 2006060825

Form CP-2/3